

**04 2000 –Masonry Systems**

Page 1 of 1

**Last Update: July 1, 2009**

A. Face Brick:

1. Face Brick needs to be included as an allowance, with actual brick selection by the owner during construction. Brick quality will be Grade: SW; Type: FBX. Typically, exterior brick will be selected to blend and be compatible with surrounding and adjacent structures. The project manager will be responsible for the final brick selection.

B. Mock-Up Panels:

1. We require 4'x6' mock-up panels (up to three) for approval of brick, mortar, and workmanship. Additional panels may be requested if necessary.

C. Winter Construction:

1. No masonry will be constructed in temperatures below freezing. No anti-freeze will be allowed.

D. Tooled Joints:

1. All joints in exterior masonry work are to be tooled.